

Scope of work – Curtain wall Replacement (2 sets)

Demolish and remove all existing components

Install new full glass doors with aluminum frames. The doors will be a 3' door and a 2' door. Existing exterior pulls will be reused. The active leaf will be the 3', right-side door when looking at the doors from the exterior.

New Von Duprin panic hardware with internal hardware to be installed on both doors. New hardware must be tied in to existing Hirsch door-access system. Hardware must be capable of being electrically dogged according to a schedule.

The new panels shall be installed as follows: door panels, insulated solid panel, insulated glass panel, insulated solid panel. They shall go as high as the current drive-it panel.

Door cores shall be a Schlage IC core and must be keyed exactly as the current doors are.

This specification is to apply to both sets of entry doors and windows. ADA requirements and exiting requirements must be adhered to.

All permits and inspections are responsibility of successful bidder

All drawings if required, are responsibility of successful bidder

Permitting questions should be directed to Codes Enforcement officer for Richland Township Ed Kline at 814-266-3070, ext. 6.

Contract must be signed by June 30, 2016 and construction and invoicing must be completed by October 31, 2016.